

**REQUEST FOR PROPOSALS**  
**Kitchen Hood Fire Suppression System Replacement**  
**FOR HAWAI'I CONVENTION CENTER**

ITEM NO.	DATE OF QUESTION / RESPONSE	QUESTION / RESPONSE	STATUS OPEN / CLOSED
Q-01	July 3, 2022	<p>Verify Tank Locations</p> <p>Tank location to be confirmed by HCC upon award of contract. Per the site visit, please assume the locations discussed.</p>	Closed
Q-02	July 3, 2022	<p>Pull Station Locations</p> <p>Pull station locations to be confirmed by HCC upon award of contract. Please assume the following:                      -The five satellite kitchens will have a total of two pull stations. The first pull station will be located by the exit door and a second nearest to the Ventmaster hood/kitchen equipment.                      -The main kitchen will have a total of four pull stations for each system. Each hood should have its own pull station closest to the Ventmaster hood/kitchen equipment. There should be a collection of pull stations for each system located at the three separate exit doors. Example: In the location with 4 hoods, there would be one near each individual panel to ensure the correct system is activated and three additional pull stations, one at each of the three exits. Labeling will be very important.</p>	Closed
Q-03	July 3, 2022	<p>Coordination work to the existing wash panel and wiring interface to new suppression tank/ control head. Exiting fire alarm, power shut downs will need to be run and landed into new system control heads</p> <p>Assume work will be required to assist with the coordination of the work detailed in the question.</p>	Closed
Q-04	July 3, 2022	<p>PCU Precipitator locations and design of protection. shut off valve Interface wiring</p> <p>Upon award of contract, locations and design of protection to be determined. Please make assumptions to complete the scope of work, per the site visit.</p>	Closed
Q-05	July 3, 2022	<p>Are the existing Fire sprinklers to be capped at drops and at shut off valve in wash panel.</p> <p>Yes, please assume plumbing work in your scope of work. The existing fire suppression system will also need to be drained. The existing shut-off valves for each kitchen is in working condition.</p>	Closed
Q-06	July 3, 2022	<p>Which hood is to receive what system?</p> <p>Please provide the following pricing for each kitchen/system:                      -The five satellite kitchens will be the Ansul/total flood system due to the various types of equipment.                      -The main kitchen to have a more isolated fire suppression system based on the type of equipment at each location. Please price accordingly per our site visit and photos.</p>	Closed